MYSORE DIVISION.

Notice dated 13th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division up to 2nd February 1928, for constructing Barr Lines for Sepoys at Nanjangud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees Two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Barr Lines for Sepoys at Nanjangud", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Estimate for constructing Barr Lines for Sepoys at Nanjangud :—

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Dismantling the existing mud houses at the proposed site, clearing jungle, levelling premisses and removing all the rubbish and debris.	Lump sum		...	100
2	Earthwork excavation for foundation and filling in basement.	C.yds.	0 3 0	68	13
3	Concrete in lime mortar	C.ft.	0 4 0	678	169
4	Burnt brick in lime mortar	„	0 5 0	1834	573
5	Burnt brick in mud superstructure ...	„	0 3 9	1610	376
6	Burnt stone slabs 6″ thick dressed ..	S.ft.	0 12 0	206	155
7	Honney wood work wrought and put up with wood oiling.	C.ft.	4 8 9	62·35	281
8	Teakwood battened door with iron fittings, etc. complete.	S.ft.	1 12 0	161	281
9	Teakwood battened windows with ¾″ dia iron bar and iron fittings, etc., complete.	„	2 8 0	52	130
10	Roofing with 1st class Mangalore tiles on teak reapers 2″ × 1″, etc., complete.	Sqr.	37 0 0	11·69	433
11	Chunam plastering	„	4 0 0	38·65	155
12	White and colour washing	„	0 6 0	38·65	15
13	Ridge tiles set in mortar	R.ft.	1 0 0	29	29
14	Providing binding wall at end of roof ..	„	0 5 0	80	25
15	Providing sinks in kitchen and bath room ...	each	5 0 0	4	20
16	Providing seats in latrine	Lump sum		...	10
17	Providing drain to lead of water from kitchen through bath and latrine and to check drain.	R.ft.	0 12 0	88	66

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
18	Flooring with gravel including watering and consolidation.	C.yds.	1 0 0	12	12
19	Providing grinding stone, pestle and mortar ..	Lump sum		...	5
20	Providing chimneys for the kitchen ..	Lump sum		...	5
21	Providing and fixing a seat of wooden pegs ...	each	1 8 0	4	6
22	Teakwood finials	„	2 8 0	2	5
23	Tarring to woodwork	Lump sum		..	10
24	Providing Mangalore ventilating tiles in kitchen.	each	3 0 0	2	6
25	Honney wood eave board ordinary including pendents.	R.ft.	0 4 0	168	42
26	Chacolate painting (silicate)	Sqr.	6 0 0	5·52	33
27	Flooring with Cuddapah slabs on 3" concrete and cement pointing, etc., complete	„	35 0 0	0·68	24
28	Burnt brick in mortar coping over compound wall.	R.ft.	0 4 0	116	29
29	Unforseen during excavation	Lump sum		...	10
	Total ...	...	...	...	3,018
	Contingencies ...	...	..	...	162
	Grand Total ...	...	...	...	3,180
	Cost of constructing one block for two sepoys is 3180.	...	...	...	...
	Therefore cost for constructing four blocks is 3180 × 4.	...	...	..	12,720
	Compensation amount	...	...	..	280
	Total ...	...	...	...	13,000
	Probable cost of the available materials from the old dismantled barr lines for sepoys to be used in the new construction.	..	..	..	800
	Total ...	...	...	...	12,200

L. A. H. WINCKLER,
Executive Engineer.